

THE ORIENTAL INSURANCE COMPANY LTD.								
A-25-27, Asaf Ali Road, New Delhi-110002								
Repair and Maintenance works At 545 Asiad Village, New Delhi.								
ELECTRICAL WORKS								
S.No		ITEM / WORKS	Units	Qty	RATES IN WORDS	RATES IN FIGURES	AMOUNT	Total
1.00		POINT WIRING						
a		5/6 amp switch socket point	Pt.	2				
		Supply & wiring of 5/6 Amp light plug point With 1.5 sq.mm PVC insulated with multistrand EBCL Wire Suitable For 120 degree Temp. and Zero Halogen copper wire including PVC conduit recessed and/or on surface including chasing of wall, filling of chases , fixing conduit on surface of wall/ceiling including fixing of saddles etc. including G.I. outlet box, modular range 6Amp switch with 5 pin 6Amp socket, modular cover plate 1.0 sq.mm PVC insulated copper earth wire etc. complete as required. NO LOOPING						
b		16 amp switch socket point	Pt.	16				
		Supply & wiring of general 16Amp power point with 4.0 sq.mm PVC insulated multistrand EBCL Wire Suitable For 120 degree Temp. and Zero Halogen copper wire including PVC conduit recessed and/or on surface including chasing of wall, filling of chases , fixing conduit on surface of wall/ceiling including fixing of saddles etc. including G.I. outlet box, modular range 16Amp switch with 6 pin 16/6Amp socket, modular cover plate 2.5sq.mm PVC insulated copper earth wire etc. complete as required. NO LOOPING						
c		AC point	Pt.	8				
		Providing and fixing 32A SPN socket outlet with wiring for AC metal clad MCB box with 32A DP including 2x6 sqm copper wire & 25m pvc pipe etc						
		Supply & wiring of AC point (32 Amps.) with 2 x 6 sq.mm PVC insulated multistrand EBCL Wire Suitable For 120 degree Temp. and Zero Halogen copper wire including PVC conduit recessed in ceiling/wall including chasing of wall, filling of chases with mortar etc. including galvanised MS outlet box, modular range 32Amp DP switch, flex outlet, cover plate, 4 sq.mm PVC insulated copper conductor earth wire etc. complete as required.						
d		Telephone point with modular plate/s with socket	Pt.	2				
2.00		MODULAR SWITCH / SOCKET CHANGE WITH MS BOX AND COVER PLATES						
		<u>Note:-</u>						
		Providing and fixing of 5/6 Amp and 15/16 amp light/power plug point With existing copper wire including G.I. outlet box after removing old ms box, modular range switch/socket with 5 pin 6Amp switch socket and 6 pin 16 Amp switch socket, modular cover plate etc. complete as required.						
a		6 Module ms box,cover plate with 16amp switch socket 1 set and 5amp switch 3 nos.	No	10				
b		8 Module ms box,cover plate with ceiling fan regulator,5amp socket 1 no and 5amp switch 4 nos.	No	10				
c		4 Module ms box,cover plate with 16amp switch/socket 1 set.	No	10				
d		6 Module ms box,cover platemith 5amp switch 4 nos and 6amp socket 1 no.	No	10				
e		4 Module ms box,cover plate with 6amp switch 3 nos.	No	10				
f		4 Module ms box,cover plate with 6amp switch socket 1 set.	No	10				
g		12 Module ms box,cover plate with ceiling fan regulator,5amp socket 1 no and 5amp switch 7 nos.	No	10				
h		Replacement of switch plates module with old one make Havels	No	75				
		TOTAL COST OF ELECTRICAL WORKS						
		TOTAL IN WORDS :-						
		CONTRACTORS NAME AND SIGNATURE WITH SEAL						