## ESTIMATE FOR THE CIVIL WORKS OF THE ORIENTAL INSURANCE COMPANY, GANDHINAGAR , BANGALORE

	PART III - CIVIL WORK FOR ADDITIONAL TOILET							
SL. NO	DESCRIPTION	UNIT	NET QUANTITY	RATE	AMOUNT			
1	MASONRY							
	Providing & Constructing Solid block masonry in							
	CM. 1:6 mix with approved quality of concrete blocks to the required sizes, including thread							
	lining of joints, necessary scaffolding curing to							
	the required period etc., complete.							
	A. 6" thick	Sft	89.00					
2	Laying PCC bed over the designated area of the							
_	toilet after removing the tiles & finished with							
	plastering including water proofing	Sft	44.00					
	compound(FOSROC /Dr.FIXIT)							
3	PLASTERING							
	Toilet wall plastering in CM. 1:3 Sponge finish.							
		Sft	282.00					
4	TILING							
	Glazed tiles to toilet walls (2'0"x1'0") over a							
	cement mortar and cement slurry including							
	supplying of all materials etc. complete. (Basic cost of Tile Rs. 45.00 /Sft.)	05:						
	COSt Of The Ns. 45.00 / Sit.)	Sft	190.00					
5	Toilet floor Providing & laying antiskid ceramic							
	tile 1'0"x1'0") over a cement mortor in CM 1:3							
	and cement slurry, joints pointed with matching							
	colour and white cement including supplying of all materials, labours etc. labour etc. (Basic cost							
	of Tile Rs. 50.00 /Sft.)							
	, ,	Sft	62.50					
	DOCUMENTS C							
6	Toilet door	_						
	Toilet door Toilet ventilator	Cft	21.25					
-	DOORS & VENTHATOR							
7	Providing & fixing RCC frame & plain Fiber							
	Shutters for toilet door including supplying of	C.	47.00					
	labours, fixing with all fixtures etc. complete.	Sft	17.00					
	Providing & fixing Aluminium louvered ventilator							
	(2'0"x1'0") including grill, painting, fixing							
8	complete.	Nos	1.00					

9	DEMOLITION WORK			
i	Labour charges for demolition-ventilator opening, including scaffolding for outside	Cft	3.75	
	removing / shimping of evicting tiles of the			
ii	removing/ chipping of existing tiles of the proposed toilet area, scaffolding (if necessary) and carting away of the debris.	LS		
				-

Say Rs